

ಚಾಮುಂಡೇಶ್ವರಿ ವಿದ್ಯುತ್ ಸರಬರಾಜು ನಿಗಮ
ನಿಯಮಿತ
(ಕರ್ನಾಟಕ ಸರ್ಕಾರದ ಸ್ವಾಮ್ಯಕ್ಕೆ ಒಳಪಟ್ಟಿದೆ)
ನಿಗಮ ಕಾರ್ಯಾಲಯ,
ಜಾವಿಸನಿನಿ, ಮೈಸೂರು-570017
Telephone No:0821-2417107



CHAMUNDESHWARI ELECTRICITY
SUPPLY CORPORATION LIMITED
(A Government of Karnataka Undertaking)
Corporate Office,
CESC, Mysuru-570017
Web Site: www.cescmysore.org
E-mail ID: gmttech@cescmysore.org

Company Identity Number[CIN]:- U40109KA2004SGC035177

No: CESC/GM(T)/DGM/AGM-2(MIS)/22-23/

1853-57

Date:

12 DEC 2022

The Chief Engineer (Ele)
O&M Zone, CESC,
Mysuru.

Sir,

Sub: Approval for availing Line clear on 66kV Hunsur-Hanagodu SC line for construction of proposed 66kV LILO line from the existing 66kV Hunsur-Hanagodu Line to the proposed 220/66/11kV receiving-Station from 17.12.2022 to 19.12.2022 from 09:00AM to 18:00 Hours.

Ref: 1. CESC/CEE/SEE(O)/AE-1/2022-23/5849-51 Dtd:07.12.2022.
2. Director(Technical) approval note dtd.09.12.2022

Anent to the above subject vide ref (1) it is stated that Chief Engineer(Ele), Transmission Zone, KPTCL, Mysore has requested to arrange concurrence for availing Line on 66kv Hunsur-Hanagodu Line from 17.12.2022 to 19.12.2022 from 09:00AM to 18:00 Hours and at present this line is under idle condition at Hunsur station end.


In continuation it is stated that for construction of proposed 66kV LILO line from the existing 66kV Hunsur-Hanagodu Line to the proposed 220/66/11kV receiving-Station at Tammadahalli for a distance of 1.490Kms in Hunsur Taluk, Mysuru District, it is required to erect one number of intermediate tower to the existing 66kV Hunsur-Hanagodu Line, and one number of existing suspension type Tower to be replaced by Anchor Tower.

Furhter it is mentioned that by considering the above work as essential & as no power supply will be interrupted during line clear period youself are also recommended for line clear and to maintain Un-interrupted Power Supply the following are the arrangements:

- Power Supply for the existing 66/11kv Hanagodu is presently fed from existing 66kv Piriapatna-Hanagodu-Ponnampete Line from 66/11kv Piriapatna S/s. The load of Piriapatna and Hanagodu S/s will be on 220kv Kushalanagar R/s and same status will continue during line clear period.
- Power Supply for the existing 66/11kv Hunsur is presently fed from existing 66kv Hunsur Bannikuppe-Hootagalli line from 220kv Hootagalli R/s and same status will continue during line clear period.

In view of the above, I am hereby directed to accord approval to avail line clear on 66kv Hunsur- Hanagodu Line from 17.12.2022 to 19.12.2022 from 09:00AM to 18:00 Hours and to instruct the concerned Executive Engineer (Ele) O & M Divisions to issue paper notification regarding line clear, to maintain uninterrupted power supply to covid hospitals and also to coordinate with KPTCL officers during line clear period.

Yours faithfully


General Manager (Tech)
CESC, Mysuru.

Copy to:

1. The Chief Engineer (Ele), Transmission Zone Mysuru, KPTCL.
2. The Superintending Engineer (Ele), O&M Circle, CESC Mysuru.
3. Executive Engineer(Ele.), O & M Division Hunsur.
3. The Assistant Executive Engineer (Ele), DCC, CESC, Mysuru.
4. PS to MD/TA to DT To place before MD and DT.
MF/OC