

ಚಾಮುಂಡೇಶ್ವರಿ ವಿದ್ಯುತ್ ಸರಬರಾಜು
ನಿಗಮ ನಿಯಮಿತ
(ಕರ್ನಾಟಕ ಸರ್ಕಾರದ ಸ್ವಾಮ್ಯಕ್ಕೆ ಒಳಪಟ್ಟಿದೆ)
ನಿಗಮ ಕಾರ್ಯಾಲಯ, ಖರೀದಿ ಶಾಖೆ,
ಚಾವಿಪನಿನಿ, ಮೈಸೂರು-570017.
Telephone No: 9448994705



CHAMUNDESHWARI ELECTRICITY
SUPPLY CORPORATION LIMITED
(A Government of Karnataka Undertaking)
Corporate Office, Procurement Section,
CESC, Mysuru-570017.
Website: www.cescmysore.org
E-mail ID: gmpure@cescmysore.org

Company Identity Number(CIN): U40109KA2004SGC035177

CESC/GM(P)/DGM(P)/AGM(P-3)/2021-22/ 22722-25

Date: 11 MAR 2022

LETTER OF INTENT TO AWARD

M/s. Prema Electricals ,
Antanahalli, Gowdagere Post,
Channarayapatna-573116.

BY REGD. POST ACK. DUE

Sir,

Sub: Providing electrical infrastructure for Ganga Kalyana Irrigation Pump Set and Water Supply Installations, by extending HT/LT lines & erection of 25KVA Distribution Transformers on Total Turnkey basis under unit rate contract in **Nuggehally Subdivision of Channarayapatna Division.**

- Ref: 1) CESC/GM(P)/DGM(P)/AGM(P-1)/2021-22/C2-5083, Date: 23-08-2021
2) Tender No. in e-portal: CESC/2021-22/EL/WORK_INDENT1423
3) Techno-Commercial Bid opened on 29-09-2021 & Price Bid opened on 20-12-2021.
4) Approved by 92nd Board meeting dated:19.02.2022
5) Note approved by Hon'ble MD, CESC dated: 10-03-2022

CESC is pleased to intent, to award the contract for execution of the work of providing electrical infrastructure by extending 11KV HT/LT lines & erection of 25kVA Distribution Transformers for **Ganga Kalyana & Water Supply** installations on Total Turnkey basis under unit rate contract in **Nuggehally Subdivision of Channarayapatna Division** jurisdiction for a period of one year at negotiated rates indicated below with total unit rate contract value limited to **150 Lakhs (One Hundred Fifty Lakhs)**, subject to terms and conditions mentioned in the Bid Document.

1) SCOPE OF WORK:

Scope of Work includes:

- Construction of HT/LT lines by using Rabbit/Weasel ACSR on 9/8 meter RCC/PSC poles and erection of 25 kVA, Star-1 Transformer on Double Pole Structure as per CESC specification.
- The contractor shall source all the other materials hardware and LT insulators as per IS specification from CESC approved vendors only.
- The hardware materials which are not in the schedule (left out materials) but are essential for completion of works are to be supplied by the agency and the rate for the same (supply & erection) will be paid as per quoted tender premium over prevailing Schedule of Rates.
- The Executive Engineer (Elec.), O & M Division shall approve and issue Work Awards for individual works on seniority basis, by giving 45 days completion period per award/work.
- Each work award may consist of either HT & DTC or DTC & LT or only LT or inclusive of all.


- 2) The contract price mentioned in the annexures is inclusive of GST, CESC will not pay any taxes and levies whatsoever in respect of this contract.
- 3) The prices for supply portion and erection portion shall be **FIRM** and valid throughout the period of contract and no price variation is allowed.
- 4) The work shall be completed in all respects within **One Year from the date of the DWA**. The completion period is extendable for further one year as per clause 13 of GCC.
- 5) Award of contract is subject to compliance of the following conditions/requirement.
 - a. The acceptance to the LOI should be sent within 20 days from the date of LOI or 7 days from the date of receipt of this letter of intent, whichever is earlier.
 - b. Contract Agreement shall be executed within 20 days from the date of issue of this LOI, for supply and erection of all equipment/materials and agreeing to follow Clause 7.0 of GCC of Section –III of the bidding document and all the terms and conditions stated elsewhere in the bid document, on Karnataka Government stamp paper of value **Rs.200/-** as per proforma mentioned in annexure of techno-commercial of the bid document with the General Manager (Procurement), CESC, Mysuru.
 - c. You are required to furnish the Bank Guarantee towards Contract Performance Guarantee issued by any Nationalized Bank/Scheduled Commercial Bank for an amount of **Rs.4,50,000/-** (Rs. Four Lakhs Fifty Thousand Only) being 3% of the Contract Value for both supply and Erection portion, which shall be **valid up to 24 months from the date of this LOI** as per Clause No. 19.0(c) of Section II, ITB and Clause-32.2 of Section III, GCC of Volume-I. The Bank Guarantee & Contract Agreement shall be furnished in the format uploaded in e-portal along with other Bid Documents.
- 6) Please note that the date of DWA is to be reckoned for all contractual purposes including delivery/completion schedule.
- 7) The firm shall procure and supply the materials from CESC approved vendors/regular suppliers to CESC only. Any proposal for procurement of materials other than the approved vendors, '**Vendor Approval**' shall be obtained from the General Manager (Tech), CESC, Mysore prior to supply of such bought out items. "The owner reserves the right to choose vendors for approval". List of Vendor Approved Firms/ Regular suppliers to CESC will be available at www.cescmysore.org.
- 8) Materials manufactured and tested as per standards shall be supplied.
- 9) Registration/Statutory Inspection Charges like inspectorate charges etc., shall be paid by the contractor. The same will be reimbursed on submission of challans for payments.
- 10) Penalty for delay in execution of work shall be as per Clause-13.0 of Section-V of SCC and clause 14.0 of GCC of Bidding Documents.
- 11) Payment will be made as per clause 8.0 of Section-V of Special Conditions of Contract with approved unit prices indicated in detailed work award.
- 12) The materials supplied shall be guaranteed as per Clause 15.0 of Section-III, GCC of Bidding Documents.
- 13) All other terms and conditions are as per the Bid Document.
- 14) The concerned Executive Engineer O&M Division/Superintending Engineer, O&M Circle will operate the rate contract as and when the work orders, for individual TC wise/LT line extension, estimates are issued and issue work award for individual works as per rules.
- 15) ESI & PF registration is mandatory as per labour act & the contractor shall produce the necessary document at the time of work award in order to regulate the same as per rules.

16) Settlement of disputes:

Any dispute or difference or claim arising out of, or in connection with, or relating to the present contract or the breach, termination or invalidity thereof, shall be referred and settled under the Arbitration center – Karnataka(Domestic and International) Rules 2012, by one or more arbitrators appointed in accordance with its rules.

Annexure – A: HT Line Extension

Sl No.	Particulars of material	Unit	Qty	Unit Price including TTK Parameters as per CSR 2018-19 (Rs.)		Awarded Price 21.50% over the CSR 2018-19 including GST,ESI & PF on Labour (Rs.)	
				Material	Labour	Material	Labour
1	9.00 Mtrs long RCC pole 145 Kg WL	Nos.	1	6516.46	1591.95	7917.49	1934.21
2	9.00 Mtrs long PSC pole 200 Kg WL	Nos.	1	3841.36	1591.95	4667.25	1934.21
3	Rabbit ACSR	km	1	38004.33	3917.06	46175.26	4759.23
4	11kV, 5kN Composite / Polymeric Pin Insulator (24mm dia FRP Rod)	Nos.	1	187.43	--	227.73	--
5	11kV, 45kN Polymeric Insulators	Nos.	1	170.77	--	207.49	--
6	11KV Horizontal cross arms with clamp, HTST , bolts &nuts of required size and washers etc for RCC pole.	Nos.	1	462.34	144.72	561.74	175.84
7	11KV Horizontal cross arms with clamp, HTST , bolts &nuts of required size and washers etc for PSC pole.	Nos.	1	456.09	144.72	554.15	175.84
8	DP Structure with RCC Pole - 9Mtr Long 145 kg WL	Set	1	18170.69	4885.06	22077.38	5935.35
9	Guy sets complete with No.15 strain insulator and concreting materials	Set	1	864.28	532.47	1050.10	646.95
10	Guy concreting with Boulders, Mud and Sand	Nos.	1	--	237.56	--	288.64
11	PG clamps for Rabbit conductor	Nos.	1	82.26	--	99.95	--
12	Spiral earth electrode	Nos.	1	171.81	83.28	208.75	101.19
13	Providing guarding at Road Crossings, Telephone Line Crossings(Labour Charges includes fixing of Cross Arms)	Mtr	1	83.30	15.09	101.21	18.33
14	Caution/Danger board as per drawing	Nos.	1	152.03	72.36	184.72	87.92
15	Anti climbing device (12 Mtrs/1 kg GI barbed wire)	kg	1	79.14	38.23	96.15	46.45




Annexure-B : DTC Supply & Erection

Sl No.	Particulars of material	Unit	Qty	Unit Price including TTK Parameters as per CSR 2018-19 (Rs.)		Awarded Price 21.50% over the CSR 2018-19 including GST,ESI & PF on Labour (Rs.)	
				Material	Labour	Material	Labour
1	9 Mt RCC DP Transformer Structure (Using 9 Mt RCC Poles)	No	1	27530.93	6180.73	33450.08	7509.59
2	11kV/433V, 25KVA, 3 Phase, 50 Cys Distribution Transformer BEE-4 Star Rated with Oil	No	1	67580.37	1023.98	82110.15	1244.13
3	Guy sets complete with No.15 strain insulator and concreting materials	Set	1	864.28	532.47	1050.10	646.95
4	Guy concreting with Boulders, Mud and Sand	Nos.	1	--	237.56	--	288.64
5	Earthing materials pipe type for grounding as per drawing (single electrode with accessories)	Set/3Nos	1	4688.97	2584.52	5697.10	3140.19
6	Caution/Danger Board	No	1	152.03	72.36	184.72	87.92
7	Anti-Climbing device(12mtrs/1Kg GI Barbed Wire) Lumpsum	kg	1	79.14	38.23	96.15	46.45
8	GI Wire 8 SWG	Kgs	1	65.91	--	80.08	--
9	Guy wire 7/10SWG	Kgs	1	67.83	--	82.41	--
10	a) LT Protection kit	No	1	1719.19	308.56	2088.81	374.90
	b) LT Wiring (LT Protection Kit) SINGLE CIRCUIT	No	1	--	--	--	--
	i) A1 Lead Wire - 50 Sq mm	Mt	1	46.14	853.32	56.06	1036.78
	ii) Heavy Duty Long barrel Cu Lugs - 50 Sq mm	No	1	41.65		50.61	
	iii) PG Clamps - Rabbit to 50 Sqmm	No	1	82.26		99.95	
	iv) Spacers for DTC Wiring	No	1	42.69		51.87	
	v. Fish Plate with necessary Clamps,bolts & nuts etc., complete (Galvanised)	No	1	156.20		189.78	
	c) LT Metering box with CTs and necessary wiring for housing ETV Meter (Please see CDS-42)	No	1	5505.35	772.76	6689.00	938.91
d) LT Electronic Tri-Vector Meter 5A, Class-0.5/1.0 accuracy	No	1	2629.28	947.52	3194.58	1151.24	
11	11 kV lightning Arrester , Metal oxide,9 kV, 5 kA	Set of 3 Nos	1	1390.14	106.49	1689.01	129.39
12	HG Fuse,11kV solid core Type	Set/3Nos	1	918.43	211.62	1115.89	257.12
13	11kV , 200Amps, Single Break GOS	Set	1	8121.10	955.71	9867.13	1161.19

Annexure-C : LT Line Extension

Sl No.	Particulars of material	Unit	Qty	Unit Price including TTK Parameters as per CSR 2018-19 (Rs.)		Awarded Price 21.50% over the CSR 2018-19 including GST,ESI & PF on Labour (Rs.)	
				Material	Labour	Material	Labour
1	8.0 Mtrs long RCC poles.115 kg WL	Nos.	1	4900.36	1272.46	5953.93	1546.04
2	8.0 Mtrs long PSC poles.200 kg WL	Nos.	1	3180.13	1272.46	3863.86	1546.04
3	Weasel ACSR	km	1	22442.10	2872.60	27267.15	3490.21
4	LT 4 Pin Cross arms with pole clamp, B&N of required size and washers etc for RCC pole	Set	1	283.23	144.72	344.13	175.84
5	LT 4 Pin Cross arms with pole clamp, B&N of required size and washers etc for PSC pole	Set	1	276.99	144.72	336.54	175.84
6	Pin Insulators 1.1 KV class with G.I.Pins, Nuts & Washers	Nos.	1	49.98	--	60.73	--
7	No.8 Strain Insulators	Nos.	1	16.66	--	20.24	--
8	Guy sets complete with 8 strain insulators & concreting materials	Set	1	864.28	532.47	1050.10	646.95
9	Guy concreting with Boulders, Mud and Sand	Nos.	1	--	237.56	--	288.64

You are requested to acknowledge this Letter of Intent to award and send your acceptance, execute the contract agreement and furnish the bank guarantee within 20 days from the date of LOI. On your acceptance for the same, the Detailed Work Award will follow.


 General Manager (Procurement),
 CESC, Mysuru

Copy:

1. Chief Financial Officer, CESC, Mysuru for information
2. Chief Engineer (Elec), CESC, O& M Zone, Mysuru for information
3. Chief General Manager(I/A), CESC, Mysuru for information
4. General Manager (Tech), Corporate Office, CESC, Mysuru for information
5. Superintending Engineer (Elec), CESC, Hassan Circle for information
6. Executive Engineer (Elec), O&M Division, Channarayapatna for further needful
7. MIS Section, to publish in cescmysore.org
8. PS to MD/DT to place before Honorable MD/Director(Technical), CESC
9. MF/OC

